

1993

COMMISSION

STATE OF MICHIGAN  
COUNTY OF LEELANAU  
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 24

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Barbara Kirt*  
REGISTER OF DEEDS

For corners in  
Leelanau

(County)

Located in:

Corner Code ##

- 1. Public Land Survey      T 31N R 11W      D-1  
                                          T \_\_\_\_\_ R \_\_\_\_\_  
                                          T \_\_\_\_\_ R \_\_\_\_\_  
                                          T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.         S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

FILE #315

LIBER 2 PAGE 12

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steven P. Bye, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

D-1: N 1/4 corner, Section 5: G.L.O. notes from Reisdon 1855 survey on South line of Section 32, T31N, R11W, "49.50 chains, Wadsworth's 1/4 section post, 20 links South"

County Surveyor's notes: iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1: N 1/4 corner, Section 5: 5/8" i.d. iron pipe found (Bramer), also 1/2" iron rod with cap #12581 found 1.24' N (Czubak). Czubak used a meander corner, West, and an axle shaft (S1/4, Sec. 32), East, to establish the terminus of this closing corner. But field notes indicate that the axle shaft was set, utilizing the found 5/8" i.d. iron pipe (Bramer) (previously)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1: N 1/4 corner, Section 5: 5/8" iron pipe (Bramer) accepted by the Leelanau County Remonumentation Peer Group, december 9, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

- 16" ash - N 87 E, 42.05'
- 12" basswood - S 79 W, 10.73'
- 10" ash - S 28 W, 2.32'
- 10" apple - N 33 W, 39.99'

Signed by *Steven P. Bye*  
Surveyor's Michigan License No. 35991

Date 12-24-93

