

**SURVEY & REMONUMENTATION**

**FEB 26 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T31N R11W</u>	<u>D-11</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Barbara Kirt 12/30/97  
Leelanau Res of Deeds 3:10 PM  
BJK Feet 9.00  
04800002 P0214 Page 1 of 1

#517

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on 12-16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-11 1/4 Corner Common to Sections 29 and 32

G.L.O. notes: Set 1/4 post  
Sugar 18 - N58W, 33 lks.  
Beech 10 - S81E, 20 lks.

Iron Found (0' Non 1983) P. Pole N25°W 25.73', 9" Maple N30°E 66.43", Double Basswood N70°E 63.93'  
1/2" Iron Rod w/cap set (0' Non 1986) 10" Maple N12°E 20.91', 10" Basswood N53°E 47.68',  
P. Pole N47°W 38.50', On fenceline North, 20' N of Kolarik Rd. West, 3.0' E of Kolarik Rd. South  
Iron Found (0' Non 1995) same wit's

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 1/4 Corner Common to Sections 29 and 32

1/2" Iron rod w/cap #28420

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY

DATE: 12-1-97  
COUNTY REP. D.M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 1/4 Corner Common to Sections 29 and 32

1/2" Iron Rod accepted as best available evidence of the position of the original corner by Leelanau County Peer Review Group, 12-1-1997 and replaced with a 3/4" i.d.

galvanized Iron pipe 1.7' long with brass cap

Witnesses: N10°E 20.90' Fd. Nail in W. Face of 12" Maple  
N50°E 47.63' Set Spike in NE Face of 16" Basswood  
N51°W 38.53' Set P.K. in NE Face of P. Pole  
S53°E 72.10' Set Spike in Face of 8" Ash

Signed by David T. Rowe  
Surveyor's Michigan License No. 11192

Date Dec 18, 1997

