

1993

1993

COMMISSION

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 25

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Barbara Kirt
REGISTER OF DEEDS

For corners in

Leelanau

(County)

Located in:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>31N</u> R <u>11W</u> | <u>E-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILE# 326

LIBER 2 PAGE 23

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven P. Bye, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1: NE corner, Section 5: G.L.O. "Corner to Sections 4 & 5 on old township line Sugar 12 - S 54 W, 28 links Do 9 - S 42 E, 42 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1: NE corner, Section 5: 5/8" iron rod with cap #19846, set in concrete

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1: NE corner, Section 5: 5/8" iron rod with cap #19846 accepted by the Leelanau County Remonumentation Peer Group, December 9, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

- Power pole - s 25 E, 69.65'
- 16" maple - S 65 W, 80.51'
- 24" maple - S 78 W, 74.37'
- 6" Tart cherry - N 35 E, 23.02'

Signed by *Steven P. Bye*
Surveyor's Michigan License No. 35991

Date 12-22-93

