

1994 DEC 30 AM 10:40

**SURVEY & REMONUMENTATION** LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corner in Leelanau County Located In: \_\_\_\_\_ Corner Code # E-12  
 APR 10 1995

*Barbara Kirt*  
 REGISTER OF DEEDS

#391

LIBER 2 PAGE 88

Register of Deeds Stamp & File Number

1. Public Land Survey Commission T 31N R 11W E-12  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Nicholas M. O'Non, in a field survey on December 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 E-12: 1/4 Corner Common to Sections 32 and 33.  
 G.L.O. Notes: Set 1/4 Section Post per A.S. Wadsworth Survey in 1851  
 Sugar 26", N 44° W, 40 Links  
 Elm 10", N 73° E, 6 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 E-12: 1/4 Corner Common to Sections 32 and 33  
 Set 1/2" x 24" rerod with cap no. 28420 at intersection of fencelines per N.M. O'Non C.S. File NO. 8102-33LL3111, November 9, 1981.  
 16" Maple, N 23° E, 6.98'  
 12" Maple, S 72° E, 15.52'  
 8" Basswood, S 45° E, 25.92'

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 LEELANAU COUNTY  
 DATE: 10-26-94  
 COUNTY REP. N.M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 E-12: 1/4 Corner Common to Sections 32 and 33.  
 Found 1/2" x 24" rerod with cap no. 28420  
 Accepted by Leelanau County Remonumentation Peer Review Group October 26, 1994. Replaced with 3/4" I.D. galvanized iron pipe 3.0' long with stamped brass cap.  
 12" Maple, N 53° E, 36.21'  
 16" Maple, N 23° E, 6.98'  
 12" Maple, S 72° E, 15.52'  
 8" Basswood, S 45° E, 25.92'



Signed by Nicholas M. O'Non Date December 29, 1994  
 Surveyor's Michigan License No. 28420

#391