

FEB 26 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>31</u> N R <u>11</u> W	<u>F-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Barbara Kirt 12/30/97
 Leelanau Rec of Deeds 3:14 pm
 BJK Fee: 9.00
 04B00002 P0221 Page 1 of 1

#524

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David T. Rowe, in a field survey on 12-16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-11 1/4 Corner Common to Sections 28 and 33

G.L.O. notes: Set 1/4 post Sugar 18 - N08°W 20lks., Beech 6 - S09°W 18 lks.

County Surveyor's Records: Brehmer 1940 Large Cedar Post, Clump Basswood N50°N 6.5', Largest triple 6", 7", 8" Elm N45°E 14.0', 6" Maple N85°E 13.6', On Fences South, North and East

Iron Stake Fd. (R.M. Harris 1986) W. Pine 6" S05°E 48.48', N. Pine 8" S39°E 66.12' 1/2" I.R. N 33.00'

R.R. Spike Fd. (J. Karr 1987) Same wit's plus S76°W 118.25' P. Pole

R.R. Spike Fd. (N. O'Non 1988)

R.R. Spike w/ "x" on Top Fd. (N. O'Non 1989)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 1/4 Corner Common to Sections 28 and 33

Found R.R. spike w/"x" in centerline of E-W Road. Old fencelines N and S

APPROVED LAND CORNER
 P.A. 345 OF 1990
 LEELANAU COUNTY

DATE: 12-1-97


COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 1/4 Corner Common to Sections 28 and 33

R.R. spike with "x" accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group, 12-1-1997 and replaced with a 3/4" i.d. galvanized pipe 3' long with a brass cap

Witnesses: S73°W 118.32' Fd. Nail in N. face of P. Pole
 S05°E 48.52' Fd. Nail in W face of 8" W. Pine
 S35°E 66.09' Fd. Nail in W face of Twin 8" R. Pine
 North 33.10' Fd. Capped Iron #25845 (R.M.H.)



Signed by [Signature]
 Surveyor's Michigan License No. 11192

Date Dec 16, 1997