

1993

COMMISSION

STATE OF MICHIGAN  
COUNTY OF LEELANAU  
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 23

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Leelanau

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 31N R 11W G-1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Barbara Kirt*  
REGISTER OF DEEDS

FILE #311

LIBER 2 PAGE 8

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Steven P. Bye, in a field survey on December 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-1: NE corner, Section 4: "Corner section 3 & 4 on old true line"

Hemlock 12 - S 15 E, 46 links  
Beech 6 - S 34 W, 35 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1: NE corner, Section 4: 1/2" iron rod found on fenceline South and occupation line West.

County Surveyor's notes: i.p. in stones 14" maple, S 88 30'W, 151.09', 12" maple S 01 00' W, 61.8'; on fenceline South and West (1933 H.H.B.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1: NE corner, Section 4: 1/2" iron rod accepted by the Leelanau County Remonumentation Peer Group, December 9, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

16 " cherry - N 15 E, 84.85'  
32" maple - South 70.55'  
6" prune - N 60 W, 52.95'  
concrete monument - East 19.55'

Signed by Steven P. Bye

Date 12-24-93

Surveyor's Michigan License No. 35991

