

SURVEY & REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF LEELANAU
 RECEIVED FOR RECORD

1994 DEC 30 AM 10:40

For corners in

Leelanau APR 10 1995 Located In: Corner Code ##
 (County)

Barbara Kirt
 REGISTER OF DEEDS

#393

LIBER 2 PAGE 90

Register of Deeds Stamp & File Number

1. Public Land Survey **COMMISSION** 31N R 11W I-12
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Nicholas M. O'Non, in a field survey on December 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-12: 1/4 Corner Common to Sections 34 and 35.
 G.L.O. Notes: Set 1/4 Section Post per A.S. Wadsworth Survey in 1851.
 Birch 14", N 9° W, 11 Links
 Hemlock 9", S 51° W, 22 Links

P.J. O'Non, Leelanau County Surveyor, Set 1/2 rered in 1963 Survey from H.H. Brehmer, previous Leelanau County Surveyor, witnesses of record. New Witnesses taken.

15" Basswood in group of 4, N 25° E, 48.58'
 20" Hemlock, N 60° E, 96.62'
 10" Elm in group of 4, East, 45.09'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12: 1/4 Corner Common to Section 34 and 35.
 Found 1/2" iron bar set by P.J. O'Non and perpetuated by many subsequent surveys.
 10" Maple, N 49° W, 9.74'
 10" Poplar, S 75° E, 2.11'
 12" Poplar, S 20° W, 7.66'
 10" Poplar, S 70° W, 4.31'

APPROVED LAND CORNER
 P.A. 345 OF 1990
 LEELANAU COUNTY
 DATE: 10-26-94
 COUNTY REP. N.M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12: 1/4 Corner Common to Sections 34 and 35
 Found 1/2" Iron Bar.
 Accepted by Leelanau County Remonumentation Peer Review Group Oct. 26, 1994. Replaced with 3/4" I.D. galvanized iron pipe 3.0' long with stamped brass cap.
 10" Maple, N 49° W, 9.74'
 10" Poplar, S 75° E, 2.11'
 12" Poplar, S 20° W, 7.66'
 10" Poplar, S 70° W, 4.31'



Signed by Nicholas M. O'Non

Date DECEMBER 29, 1994

Surveyor's Michigan License No. 28420