

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 32 N. R. 10 W.	C-6; C-7
2. PROPERTY CONTROLLING IN SECTION 18	T. 32 N. R. 10 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 24, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-6 Fd. sq. conc. mon. for E $\frac{1}{4}$  corner Sec. 18, T32N-R10W, per survey by H. H. Brehmer, Co. Surveyor, 1951.
- C-7 Fd. 3/4" pipe for SE corner of Sec. 18, T32N-R10W, that fits survey by H. H. Brehmer, Co. Surveyor, 1951.
- 15 Drove 5/8" reroed by old fence corner, fence remains N & E. H. H. Brehmer survey of Sec. 19, calls for fence corner at corner in 1937; we fit Brehmer's distance to fd. corners a  $\frac{1}{4}$  mile E & S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6	C-7	15
Fd. sq. conc. mon. 0.6' below BT surface; raised flush w/3/4" pipe	Fd. 3/4"x36" pipe; added cedar post w/loc. tag	Drove 5/8"x40" reroed & set cedar post w/loc. tag
P. Pole S20 <sup>0</sup> W 83.31	5" Hemlock N62 <sup>0</sup> E 24.37	18" W. Pine N12 <sup>0</sup> E 107.98
26" Maple N64 <sup>0</sup> W 87.83	18" Maple S70 <sup>0</sup> E 17.30	4" Cedar N42 <sup>0</sup> E 52.00
Ctr. N-S b'top rd. is E 6.5'	P. Pole S32 <sup>0</sup> E 48.55	12" W. Pine S80 <sup>0</sup> E 91.48
Set cedar post w/loc. tag West 33'	8" Maple S65 <sup>0</sup> W 64.40	
	Fd. rd. conc. mon. Due E 33.0	

SIGNED BY Carl F. Roser 5/14/80 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

LEELANAU TOWNSHIP  
LEELANAU COUNTY