

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 32 <sup>N.</sup> R. 10	B-7
2. PROPERTY CONTROLLING IN SECTION 18 _____	T. 32 <sup>N.</sup> R. 10	10; 12
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> S. _____ R. _____ <sup>E.</sup> W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on October 24, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-7 Fd. sq. conc. mon. for S 1/4 corner Sec. 18, T32N-R10W, per survey by H. H. Brehmer, Co. Surveyor, 1951.
- 10 Drove 5/8" rerod for S 1/8 corner on the W line of Sec. 18; per measured distance between W 1/4 corner & U.S.M.C. to S, prorated to U.S. distance per acreage amounts on G.L.O. plat.
- 12 Established S 1/8 corner on N-S 1/4 line, Sec. 18, T32N-R10W, per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7	10	12
Fd. sq. conc. mon.; added cedar post w/loc. tag	Drove 5/8"x36" rerod & set cedar post w/loc. tag	Drove 5/8"x36" rerod w/RIS cap (buried 0.3)
10" Maple S25°W 44.23	9" Maple N70°W 39.2	20" Oak S88°W 34.27
6" Maple N45°W 48.35	7" Maple S80°W 20.7	6" Oak S67°E 19.35
*14" dead Maple S40°W 18.7	15" Maple S60°E 34.3	12" W.Pine N37°E 44.57
Q N-S Rd. Due E 18'±	Ctr. E-W hiking trail North 10'±	Set ced. post w/loc. tag West 33'
*Brehmer witness		Ctr. N-S gravel road West 6'

SIGNED BY Carl F. Roser DATE 5-14-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

LEELANAU TOWNSHIP  
LEELANAU COUNTY