

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---|---------------|---------------------------|
| 1. PUBLIC LAND SURVEY _____ T. _____ N. S. R. _____ E. W. | | |
| 2. PROPERTY CONTROLLING IN SECTION <u>18</u> T. <u>32</u> N. S. R. <u>10</u> W. | | <u>5; 8</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION <u>18</u> T. <u>32</u> N. S. R. <u>10</u> W. | | <u>YY = 966.1' N of 8</u> |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on October 29, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 30, 1979, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5 Fd. sq. conc. mon. for N 1/8 corner on N-S 1/4 line, Sec. 18, T32N-R10W, per survey by H. H. Brehmer, Co. Surveyor, 1951.
- 8 Fd. sq. conc. mon. for W 1/8 corner on E-W 1/4 line, Sec. 18, T32N-R10W, per survey by H. H. Brehmer, Co. Surveyor, 1951; corner is in wet hole in swamp.
- YY Fd. sq. conc. mon. for the NE corner of the S 28.75 acres of the W frl. 1/2 of the NW frl. 1/4 of Sec. 18, T32N-R10W, per survey by H. H. Brehmer, Co. Surveyor, 1951.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| 5 | 8 | YY |
|---|---|--|
| Fd. sq. conc. mon.; set cedar post w/loc. tag | Fd. sq. conc. mon.; added cedar post w/loc. tag | Fd. sq. conc. mon. & added cedar post w/loc. tag |
| 12" W. Birch S60°E 12.05 | 6" Cedar N03°E 31.1 | 10" Maple N12°E 20.40 |
| 5" Ash S60°W 10.64 | 9" Cedar S87°W 24.3 | 5" Hemlock S25°E 9.94 |
| 13" Maple N22°E 19.60 | 8" Cedar S05°E 15.0 | 10" Maple S60°W 9.12 |
| Ctr. N-S gravel road Due W 45'± | | |

SIGNED BY Carl F. Roser 5-14-80 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

LEELANAU TOWNSHIP
LEELANAU COUNTY