

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>32</u> <sup>N.</sup> <u>11</u> <sup>W.</sup>	M-5; M-6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 29, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-5 Found square concrete monument for NE corner of Sec. 13, T32N-R11W, per survey by H. H. Brehmer, Co. Surveyor, 1951. Corner falls on SW slope of ridge NW & SE. The NW corner of Sec. 18, T32N-R10W is N01°13'44"E 331.07'.

M-6 Found square concrete monument for E½ corner Sec. 13, T32N-R11W, per survey by H. H. Brehmer, Co. Surveyor, 1951. Fits U.S.B.T. pine stump NE, showing excellent lower face with scribes and notch. The W¼ corner of Sec. 18 T32N-R10W is N01°13'00"E 330.11'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5	M-6
Fd. sq. conc. mon; added cedar post w/loc. tag 11" Hemlock N10°W 11.15 11" Ironwood S55°E 21.57 17" Hemlock S33°W 19.06	Fd. sq. conc. mon; added cedar post w/loc. tag 6" W. Birch N84°E 16.23 10" Maple N06°W 9.04 9" Maple S50°E 31.2 U.S.B.T. W. Pine Stp. N88°E 16.7

SIGNED BY Carl F. Roser 5-14-80 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

LEELANAU TOWNSHIP  
LEELANAU COUNTY