

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF LEE LANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 24

Barbara Kirt
REGISTER OF DEEDS

FILE #316

LIBER 2 PAGE 13

Register of Deeds Stamp & File Number

For corners in

Leelanau
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 32N R 11W E-13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Steven P. Bye, in a field survey on December 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-13: SE corner, Section 32: G.L.O. Risdon 1855 survey "80.50 to old corner of section 32 & 33.
Sugar tree 8 for corner
Do 8, N 14 E, 43 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13: SE corner Section 32: 3/4" square iron bar in concrete an occupation line West and centerline of gravel road extension North

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13: SE Corner, SECTION 32: 3/4" square iron bar in concrete accepted by the Leelanau County Remonumentation Peer Group, december 9, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

- 20" Ash - S 10 W, 24.35'
- 15" ash - S 70 W, 50.96'
- 28" maple - S 73 E, 125.96'
- Power pole - S 56 E, 83.58'
- 16" apple - N 56 W, 89.59'

Signed by Steven P. Bye

Date 12-24-93

Surveyor's Michigan License No. 35991

