

1993

COMMISSION

STATE OF MICHIGAN
COUNTY OF LEELANAU
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 23

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Leelanau
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 32N R 11W F-13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Barbara Kirt
REGISTER OF DEEDS

FILE #308

LIBER 2 PAGE 5

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Steven P. Bye, in a field survey on December 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13: S 1/4, Section 33: G.L.O. Risdon survey 1855
"Old 1/4 section corner, old witness trees standing, course and distance not correct"

Elm 12 - N 32 W, 11 links
Do 12 - N 62 E, 35 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13: S 1/4, Section 33: iron rod with cap #19846 2.5' below the surface of Ranger Road, and on fenceline E-W

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13: S 1/4, Section 33: iron rod with cap #19846 accepted by the Leelanau County Remonumentation Peer Group, December 9, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

26" maple - S 77 W, 45.07'
6" apple - South 29.29'
10" basswood - N 26 E, 101.08'
NE corner of barn - S 27 W, 111.40'

Signed by *Steven P. Bye*
Surveyor's Michigan License No. 35991

Date 12-24-93

