

# SURVEY & REMONUMENTATION

MAR 04 1999

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                    |                             |               |  |
|------------------------------------|-----------------------------|---------------|--|
| Leelanau                           | Located In:                 | Corner Code # |  |
| (County)                           |                             |               |  |
| 1. Public Land Survey              | T <u>32</u> N R <u>11</u> W | <u>G-7</u>    |  |
|                                    | T ___ R ___                 |               |  |
|                                    | T ___ R ___                 |               |  |
|                                    | T ___ R ___                 |               |  |
| 2. Property Controlling in Section | S ___ T ___ R ___           |               |  |
|                                    | S ___ T ___ R ___           |               |  |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___           |               |  |
|                                    | S ___ T ___ R ___           |               |  |

Barbara Kirt 12/31/98  
Leelanau Reg of Deeds 9:58 am  
BJK Fee: 9.00  
04B00002 P0296 Page 1 of 1

#599

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on 11-30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| 1  | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

**A. Description of original monument and accessories and/or subsequent restoration:**

G-7 Corner common to Sections 15, 16, 21 and 22:

G.L.O. Notes: 1855 Set Post on N. Border of Swamp - 10" Hemlock N33°E 13 lks., 16" Hemlock S33°W 28 lks.

County Records: 1912 Fd. Stumps of Original Witnesses - N.B. 6" Basswood N86°30'W 114 lks.  
1930's H. Brehmer - Fd. Cedar Stake - 8" Cedar N31°30'E 39.1', 6" Cedar S73°30'W 14.15', 6" Cedar S86°30'E 47.5'.

1 1/2" Iron Pipe in Concrete Found - 1984 N. 0'Non  
(Section A. continued below)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-7 Corner common to Sections 15, 16, 21 and 22:

Found Concrete Monument.

(Section A. continued)

1 1/2" Iron Pipe in Concrete Found - 1986 N. 0'Non  
Concrete Monument Found - 1989 N. 0'Non

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY**

DATE: 12-08-98

COUNTY REP. [Signature]

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-7 Corner common to Sections 15, 16, 21 and 22:

Concrete Monument accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Group, 12-08,1998 and was left in place.

Witnesses: S77°W 14.28' - Found P.K. Nail in N.W. Face 12" Cedar  
N42°W 10.20' - Found Nail in N.E. Face 8" Cedar  
S13°W 18.70' - Set Nail in W. Face Blazed 6" Cedar  
S15°E 39.36' - Set Nail in E. Face 8" Cedar  
N60°E 8.61' - Set Nail in S.E. Face 4" Ash

Signed by David T. Rowe  
Surveyor's Michigan License No. 11192

Date Dec 29, 1998

