

**SURVEY &
REMONUMENTATION**

MAR 04 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

| | | |
|---------------------------------------|-----------------------------|---------------|
| <u>Leelanau</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>32</u> N R <u>11</u> W | <u>G-8</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

#600

Barbara Kirt 12/31/98
Leelanau Reg of Deeds 9:58 am
BJK Feet 9.00
04B00002 P0297 Page 1 of 1

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David T. Rowe, in a field survey on 12-10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

G-8 1/4 Corner common to Sections 21 and 22:

G.L.O. Notes: 1855 Set 1/4 Section Post - 15" Birch N39°E 35 lks., 28" Hemlock S22°W 8 lks.
County Records: 1930's H. Brehmer - Fd. Old Square Cedar Stake buried in road - 14" Beech S19°E 41.8', 14" Beech S35°30'W 55.0', 18" Hemlock N29°15'W 34.1'.
1991 G. Stowe - Fd. 1/2" Iron Pipe - 16" Beech South 23.77', 18" Maple N38°E 34.15', 10" Maple S59°E 59.49'.

Iron Found - 1977 T. Weinert
3/4" Iron Found - 1986 N. O'Non

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 1/4 Corner common to Sections 21 and 22:

Found 3/4" x 24" Iron Pipe 5.0' S. C/L Road, pieces of cedar stake found inside Iron Pipe.

APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY

DATE 12-10-98
COUNTY REP. H.M.C. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 1/4 Corner common to Sections 21 and 22:

3/4" x 24" Iron Pipe accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Group, 12-10,1998 and replaced with 3/4" i.d. galvanized 36" long Iron Pipe with a brass cap in a pavement box.

Witnesses: S08°W 23.72' - Set Nail in E. Face Blazed 18" Beech
N37°E 34.19' - Found Spike in N.W. Face Blazed 18" Maple
S65°W 48.31' - Set Nail in S.E. Face 10" Yellow Birch
N57°W 96.85' - Set Nail in N.E. Face 10" Ash

Signed by David T. Rowe
Surveyor's Michigan License No. 11192

Date Dec 29, 1998

