

**SURVEY &
REMONUMENTATION**

MAR 04 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>32</u> NR <u>11</u> W	<u>H-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Barbara Kirt 12/31/98
Leelanau Res of Deeds 9:59 am
BJK Feet 9.00
04800002 P0300 Page 1 of 1

#603

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David T. Rowe, in a field survey on 12-10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-7 1/4 Corner common to Sections 15 and 22:
G.L.O. Notes: 1855 Set 1/4 Section Post - 12" Hemlock N64°W 23 lks., 8" Hemlock S49°E 30 lks
County Records: 1912 F. Greene - Fd. Stone Corner at S. End of Old Stone Fence.
Iron Pipe Found - 1974 T. Weinert
Iron Bar Found - 1977 T. Weinert
Iron Found - 1989 G. De La Mater
Iron Found - 1990 G. Stowe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 1/4 Corner common to Sections 15 and 22:
Found 1" Iron Pipe 18" long 10.0' W. C/L Road, Stone Fence to W-E.

APPROVED LAND CORNER
P.A. 345 OF 1990
LEELANAU COUNTY
DATE: 12-10-98
COUNTY REP. H.M. O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 1/4 Corner common to Sections 15 and 22:
1" Iron Pipe accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Group, 12-16,1998 and replaced with 3/4" i.d. galvanized 36" long Iron Pipe with a brass cap in a pavement box.
Witnesses: S58°E 43.15' - Found Spike in S.W. Face 6" Ash
S68°E 52.81' - Found Spike in S.W. Face 6" Cedar
N55°E 80.90' - Set Nail in S.E. Face 4" Cedar
S84°W 54.86' - Found Spike in S.E. Face Blazed Triple 4" Appl

Signed by David T. Rowe
Surveyor's Michigan License No. 11192

Date Dec 29, 1998

