

**SURVEY &  
REMONUMENTATION**

MAR 04 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Leelanau Located In: Corner Code #  
(County)

1. Public Land Survey T 32NR 11W I-7  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_

2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

Barbara Kirt 12/31/98  
Leelanau Reg of Deeds 10:00 am  
BJK Fee: 9.00  
04600002 P0302 Page 1 of 1

#605

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on 11-25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-7 Corner common to Sections 14, 15, 22 and 23:  
G.L.O. Notes: 1855 Set Post - 9" White Ash N19°W 118 lks.  
County Records: 1930's H. Brehmer - Fd. Cedar Stake in N-S Fenceline.  
Monument Found - 1975 T. Weinert  
Concrete Monument Found - 1977 T. Weinert  
Iron Pipe Found - 1989 N. O'Non  
Iron Found - 1993 G. Stowe  
3/4" Pipe & Cedar Post Found - 1997 Gourdie/Fraser & Associates

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 Corner common to Sections 14, 15, 22 and 23:  
Found 1" o.d. Iron Pipe 3.4' long, 0.2' S15°E Squared Cedar Post, on old N-S Fenceline, corner is in marsh area.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY  
DATE: 12-08-98  
COUNTY REP. N.M.O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 Corner common to Sections 14, 15, 22 and 23:  
1" o.d. Iron Pipe accepted as a careful and faithful perpetuation of the position of the original corner by the Leelanau County Peer Group, 12-08,1998 and replaced with 3/4" i.d. galvanized 36" long Iron Pipe with a brass cap.  
Witnesses: N78°W 8.79' - Found Spike in S. Face Blazed 16" Ash  
S02°E 9.02' - Found Nail in Face Blazed 20" Ash  
N60°E 19.67' - Found Spike in N.W. Face Blazed 16" Ash  
N30°W 41.53' - Set Spike in S.W. Face 16" Ash

Signed by David T. Rowe  
Surveyor's Michigan License No. 11192

Date Dec 29, 1998

