

**SURVEY & REMONUMENTATION**

MAR 04 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Leelanau Located In: Corner Code #  
(County)

1. Public Land Survey T 32NR 11W I-8  
T R  
T R  
T R

2. Property Controlling in Section S T R  
S T R

3. Miscellaneous Property in Sec. S T R  
S T R

Barbara Kirt 12/31/98  
Leelanau Res of Deeds 10:00 am  
BJK Feet 9.00  
04B00002 P0303 Page 1 of 1

#606

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on 11-25, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-8 1/4 Corner common to Sections 22 and 23:  
G.L.O. Notes: 1855 Set 1/4 Post - 9" Hemlock N46°E 21 lks., 9" Cedar S48°W 13 lks.  
County Records: 1905 F. Greene - Fd. Old Stake In Position - N.B. 11" Hemlock N44°E 41'.  
Iron Pipe Found - 1977 T. Weinert

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8 1/4 Corner common to Sections 22 and 23:  
Found 1 1/2" x 7' Well Point.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY

DATE: 12-08-98  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8 1/4 Corner common to Sections 22 and 23:  
1 1/2" x 7' Well Point accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Group, 12-08,1998 and replaced with 3/4" i.d. galvanized 36" long Iron Pipe with a brass cap.

Witnesses: N64°E 57.70' - Found Spike in N.W. Face Blazed 8" Cedar  
N38°E 43.03' - Set Spike in E. Face Blazed 6" Ash  
N09°E 30.86' - Found Spike in E. Face Blazed 8" Ash  
N42°W 42.28' - Found Spike in S.W. Face Blazed 10" Aspen  
S01°E 21.90' - Found Spike in W. Face Blazed 6" Aspen

Signed by David T. Rowe  
Surveyor's Michigan License No. 11192

Date Dec 29, 1998

