

SURVEY &  
REMONUMENTATION

MAR 04 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 32NR 11W	I-9
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Barbara Kirt 12/31/98  
Leelanau Reg of Deeds 10:00 am  
BJK Fee: 9.00  
04B00002 P0304 Page 1 of 1

#607

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on 11-25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-9 Corner common to Sections 22, 23, 26 and 27:

G.L.O. Notes: Set Post - 14" White Ash N39°E 26 lks., 14" White Ash S71°W 9 lks.  
Set Monument - 1972 J. Wilcox - located where the remains of an old cor. post was, after talking to a Mr. Kilcherman, a man about 80 years old, told him that 30 or 40 years ago his dad had that fence corner established by the Co. Surveyor (Mr. Green) for the purpose of setting the fence cor. at the section corner. After looking at Green's old records, He determined that the old corner post is the

(Section A. continued below)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Corner common to Sections 22, 23, 26 and 27:

Found Concrete Monument 22' South of C/L Road.

(Section A. continued)

section corner.

Concrete Monument Found - 1977 T. Weinert

Iron Found - 1988 N. O'Non

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY

DATE: 12-8-98

COUNTY REP. W.M.O'Non

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Corner common to Sections 22, 23, 26 and 27:

Concrete monument accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Group, 12-08,1998 and was left in place.

Witnesses: West 10.00' - Found Spike in S. Face 30" Maple  
S20°W 44.03' - Found Spike in N.E. Face 12" Maple  
S05°W 33.12' - Found Capped Iron P.S. #31611  
S88°E 34.36' - Set Spike in S. Face Twin 8" Maple  
N30°E 78.97' - Set Nail in S.E. Face 6" Cherry

Signed by David T. Rowe  
Surveyor's Michigan License No. 11192

Date Dec 29, 1998

