

MAY 16 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Leelanau (County)	Located In:	Corner Code #
1. Public Land Survey	T32N R11W	I-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Barbara Kirt 01/09/97  
 Leelanau Reg of Deeds 10:00 am  
 EJK Feet 9.00  
 04800002 F0178 Page 1 of 1

#481

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on Oct. 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11: Corner common to Sections 26, 27, 34 and 35:  
 G.L.O. Notes: Set Post  
 Hemlock 8 - N46°W, 23 lks.  
 Birch 10 - N68°E, 30 lks.

County Surveyors Records:

Concrete tile monument @ N.W. corner of Section 35

Concrete monument found (T. Weinert 1975, N. O'Nono 1990 and 1995)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11: Corner common to Section 26, 27, 34 and 35:

Concrete tile monument found with a 3/8" iron in center, in line with an old east-west fence.

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 LEELANAU COUNTY

DATE: 10-30-96  
 COUNTY REP. Tom O'Nono

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11: Corner common to Sections 26, 27, 34 and 35:

Concrete tile monument accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Review Group, October 30, 1996.

- Witnesses: N42°E, 37.44' - Found spike in 5" hemlock  
 S19°E, 6.02' - Found spike in east root of 5" yellow birch  
 S67°E, 22.10' - Found spike in 3" balsam fir  
 S28°W, 27.51" - Set spike in 4" hemlock  
 N15°W, 71.48' - Set spike in 16" red maple

Signed by David T. Rowe  
 Surveyor's Michigan License No. 11192

Date Dec 17, 1996

