

**SURVEY & REMONUMENTATION**

MAR 04 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lee Lanau SECTION  
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 32N R 11W J-7
- T      R      \_\_\_\_\_
- T      R      \_\_\_\_\_
- T      R      \_\_\_\_\_
- 2. Property Controlling S      T      R      \_\_\_\_\_
- in Section S      T      R      \_\_\_\_\_
- 3. Miscellaneous S      T      R      \_\_\_\_\_
- Property in Sec. S      T      R      \_\_\_\_\_

Barbara Kirt 12/31/98  
Leelanau Reg of Deeds 10:01 am  
BJK Feet 9.00  
04800002 P0306 Page 1 of 1

#609

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on 11-30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-7 1/4 Corner common to Sections 14 and 23:  
G.L.O. Notes: Set 1/4 Section Post - 15" Birch N48°E 36 lks., 10" Sugar S10°W 15 lks.  
County Records: 1905 F. Greene - Pd. Stone  
Concrete Monument Found - 1972 P. O'Non  
Concrete Monument Found - 1993 M. Harris  
Concrete Monument Found - 1998 N. O'Non

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7 1/4 Corner common to Sections 14 and 23:  
Found Concrete Monument 5.3' ± W. of Fenceline South and 1.5' ± N. of Stone Fenceline East

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY  
DATE: 12-08-98  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 1/4 Corner common to Sections 14 and 23:  
Concrete Monument accepted as the best available evidence of the position of the original corner by the Leelanau County Peer Group, 12-08,1998 and was left in place.  
Witnesses: S18°W 43.72' - Found Nail in W. Face 20" Maple  
N81°E 17.86' - Found Spike in S. Face Blazed 10" Maple  
N40°E 22.30' - Found Nail & Washer in N.W. Face Blazed 12" Maple  
S70°W 32.05' - Found Nail in N. Face 16" Maple  
S75°W 57.77' - Found Nail & Washer in N. Face 14" White Pine

Signed by David T. Rowe  
Surveyor's Michigan License No. 11192

Date Dec 29, 1998

