

**SURVEY & REMONUMENTATION**

MAR 04 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Leelanau (County) Located In: Corner Code #

1. Public Land Survey T32N R11W J-9  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_

2. Property Controlling in Section S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous Property in Sec. S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

Barbara Kirt 12/31/98  
Leelanau Reg of Deeds 10:02 am  
BJK Fee: 9.00  
04800002 P0307 Page 1 of 1

#610

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David T. Rowe, in a field survey on 11-25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-9 1/4 Corner common to Sections 23 and 26:

G.L.O. Notes: 1855 Set 1/4 Post - 20" White Ash N67°E 12 lks., 6" Sugar S72°W 29 lks.  
County Records: 1905 F. Greene - Fd. Stone  
1939 H. Brehmer - Fd. Stone With Cross - 14" Maple S21°W 13.3',  
24" Maple S68°E 18.5', 24" Maple N05°E 53.3'.  
Stone With "X" Found - 1972 J. Wilcox  
Stone With "X" Found - 1993 M. Harris

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 1/4 Corner common to Sections 23 and 26:

Found Stone With Cut "X" On Top.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
LEELANAU COUNTY

DATE: 12-08-98  
COUNTY REP. [Signature]



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 1/4 Corner common to Sections 23 and 26:

Stone With Cut "X" On Top accepted as a careful and faithful perpetuation of the position of the original corner by the Leelanau County Peer Group, 12-08,1998 and replaced with a 3/4" i.d. galvanized 36" long Iron Pipe with a brass cap.

Witnesses: S65°E 18.49' - Found Nail & Washer in N. Face Blazed 36" Maple  
S26°W 13.73' - Found Nail & Washer in E. Face Blazed 14" Maple  
S68°W 29.30' - Found Nail & Washer in N.W. Face Blazed 20" Maple  
N09°E 16.53' - Found Nail & Tag P.S. #25845 in W. Face P. Pole

Signed by David T. Rowe  
Surveyor's Michigan License No. 11192

Date Dec 29, 1998