

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 123

For corners in

Lenawee  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T-5-S R-1-E D-1
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec S T R

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

13 NOV 96 9:05 A.M.

JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 17 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Not set on original G.L.O. survey.  
 April 1944, W.E. Frazier did a survey in Section 5 that shows a fence on the 1/4 line.  
 1955, While employed by W.E. Frazier, I set a big spike in line with an old fence line to the South, 204.00 West of iron pipe at D-13, T4S-R1E.  
 August 1973, K.L. Suydam set a RR.spike in the pavement 204.00 feet West from iron pipe at D-13, T4S-R1E.  
 October 1976 and March 1979, I found the RR.spike and sighted to it from the South.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 1994, Found a C.M.P. crossing under the road 201' West of D-13, T4S-R1E.  
 July 17, 1996, I set a 3/4" X 3' gas pipe capped G.E.R. 13040 in a monument box 204.00 West of D-13, T4S-R1E and on line between the Jackson County corners C-1 and D-1, T4S-R1E as approved and monumented.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.  
 Dbl. hd. nail & re-mon tag in E. face Elec. pole N 15° E 78.41  
 Dbl. hd. nail & re-mon tag in E. face Elec. pole N 45° E 71.44  
 Dbl. hd. nail & re-mon tag in N. face Elec. pole S 65° E 72.50  
 Dbl. hd. nail & re-mon tag in E. face Elec. pole S 10° E 244.98  
 "X" cut on C.M.P. S 20° E 19.29  
 Approved Jackson Co. monument @ D-13, T4S-R1E East 204.00



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 7-16-1996

Signed by Glenn E. Richard Date 10-25-96  
 Glenn E. Richard

Surveyor's Michigan License No. 13040