

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 120

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T-5-S R-1-E F-1
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
LENAWEE COUNTY

Filed

13 NOV 96 9:04 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Glenn E. Richard, in a field survey on June 3 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set on Original G.L.O. survey.

May 1946, W.E. Frazier notes show "o" (No description of monument) in line with fence South.

March 15, 1972, K.L. Suydam set 1" iron shaft using NW. corner Section 4 and Plat monuments of Plat of Royal Shores, Lake Columbia and in line of old fence South (now gone).

May 1972, I found the iron shaft in the pavement and recorded it in L. 1, P. 437.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 1994, I found the iron shaft and took some witnesses prior to road re-construction.

February 1, 1996, Set P.K. nail on line between Jackson County Standard Re-monumentation corners E-13 & F-13, T4S-R1E as approved by the Jackson County Peer Group.

It falls 5.27 North of corner recorded in L. 1, P. 437.

June 3, 1996, Set 3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in between several stones & bent top to correct location in monument box in place of the P.K. nail set on 2-1-96.

The iron shaft recorded in L.1, P.437 is still in the pavement under 4" of new asphalt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Re-rod North 30.78

Re-rod in concrete inside P.V.C. south 38.09

Head of 60d spike in W. side of 24" Oak South 240.73

(all of the above are on the same line)

Dbl. hd. nail & disc in S. Side of Elec. pole S 80° W 128.93

F-13, T4S-R1E East 152.87



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 07-16-96

Signed by Glenn E. Richard Date 10-25-96
Glenn E. Richard

Surveyor's Michigan License No. 13040