

MAY 18 1997

COMMISSIONER

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 131

For corners in

Lenawee Located In: Corner Code #

- 1. Public Land Survey T-5-S R-1-E G-1
2. Property Controlling in Section S-T-R
3. Miscellaneous Property in Sec S-T-R

STATE OF MICHIGAN LENAWEE COUNTY FILED

13 NOV 96 9:06 A.M.

Register of Deeds JEANETTE D. KNOX REGISTER OF DEEDS

- 4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on January 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked in the cell at row 2, column G.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, Robert Clark set post 130 links West of post. Cor. Sections 3 & 4, W. Oak 12, S 89 E 37 October 1883, James Blair describes the corner as iron, brick & stone. September 1977, I set a P.K. nail at record jog 130 links (85.80') West of RR spike found at G-13, T4S-R1E on line to found P.K. which someone had set for F-13, T4S-R1E which was the same line as the northerly extension of a line between the G-3 and G-2, T5S-R1E corners. I recorded it in L4, P. 37. August 1994, I found iron pipe in place of P.K. and set re-rod 40.31 South on line to G-2. With my approval, Dean Gutekunst, Jackson County Surveyor, dug with back hoe as part of his work on G-13, T4S-R1E but didn't find anything else.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

January 22, 1996, Set P.K. nail on extension of line from G-2 through the re-rod and on line between Jackson County re-monumentation corners F-13 & G-13, T4S-R1E, as approved by the Jackson County Peer Group. July 17, 1996, Set 3/4" X 3' gas pipe capped G.E.R. 13040 in monument box which is 0.67 South of the location recorded in L.4, P.37.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner. SW. corner of house foundation N 60° W 138.18 SE. corner of house foundation N 45° W 107.84 SW. corner of house foundation North 68.55 SE. corner of house foundation N 35° E 84.73 SW. corner of house foundation N 60° E 120.32 SE. corner of house foundation N 65° E 155.37 Jackson County Standard Re-monumentation corner in monument box at G-13, T4S-R1E East 86.15



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 07-16-96

Signed by Glenn E. Richard Date 10-11-96 Glenn E. Richard

Surveyor's Michigan License No. 13040