

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

8 JUL 97 1:02 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

For corners in	Located In:	Corner Code #
<u>Lenawee</u>		
(County)		
1. Public Land Survey	T - 5-S R - 1-E	H-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on May 19 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set on original G.L.O. survey.
1883 James Blair stake found, set iron 3/4 W (24.91) of Jackson corner.
1995 Dean Gutekunst dug in conjunction with digging for the S 1/4 corner of Section 34 T 4 S, R 1 E and found a red stone 2' below the blacktop surface with lighting rod at the southeast corner of the stone. Set 3/8" rod on top of stone at the surface.
November 9, 1995 I witnessed the 3/8" re-rod set by Dean Gutekunst.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 15, 1997 Set control North and South to save point for paving.
May 16, 1997 Set point in base course of asphalt 0.31 south of original location to be on line between Jackson Co. corners G-13 and H-13 (L 1501 P 1111) T 4 S, R 1 E
May 19, 1997 Jackson Co. Rd. Comm. installed a monument box
May 19, 1997 I set a 3/4" X 3' gas pipe in monument box using the control set up on May 15, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe stamped P.S. 13040 in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.
SE corner of SE leg at top of bolt flange of Electric Tower S 35° W 130.63
" X " cut on W end of CMP S 50° W 26.86
" X " cut on W end of CMP S 10° E 17.90
Survey marker spike & Re-mon tag in W side E.P. South 51.22
Survey marker spike & Re-mon tag in W side 24" Pine S 25° E 88.05
Fd nail in E.P. N 55° E 87.42
H-13 T 4 S, R 1 E. East 23.33 (Jackson Co. Rec. 23.41)

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

SURVEY &
REMONUMENTATION

AUG 25 1997

COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 6-3-97

Signed by Glenn E. Richard Date 6-9-97
Glenn E. Richard

Surveyor's Michigan License No. 13040