

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

8 JUL 97 1:02 P.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 5-S R - 1 - E	I-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on May 19, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 Robert Clark Intersect N. Bdg. 64 lks E. of post
 Set post at intersection, corner sections 2 & 3 B. Oak 16 West 28 Hickory 6 S 45° W 50
 1873 B. Kent Co. Surveyor located the corner " by the Witness trees"
 1883 +/- James Blair survey called for "stake & stone, government tree & stump standing"
 Early 1900's J. L. Richard record same as Blair's
 1956 I dug for the corner but didn't find anything.
 1974 I set a iron pipe 42.24 (G.L.O. rec.) east of found iron at I-13 T4 S, R 1 E and capped RLS 7863 (Richard Gutekunst) and recorded it in L 3, P 29.
 Sept. 24, 1996 I found the iron pipe and witnessed it. Jackson Co. Rd. Comm. dug large hole but we didn't find anything other than the iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 16, 1997 Set point in base course of asphalt 0.03 south of original location to be on line between Jackson Co. corners I-13 and J-13 T 4 S, R 1 E.
 May 19, 1997 Jackson Co. Rd. Comm. installed a monument box. I set a 3/4" X 3' gas pipe capped G.E.R. 13040 in the monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 "X" cut on W. end CMP S 45° W 34.12
 "X" cut on E. end CMP S 20° W 14.80
 Fd nail & washer in 20" Oak S 45° E 39.25
 Re-rod South 36.32 as witness point and on line with (next witness below)
 Dbl. hd. nail & disc in face of 24" Oak South 70.17
 Jackson Co. monument stamped 18658 at I-13 T 4 S, R 1 E in monument box
 West 42.22

**SURVEY &
 MONUMENTATION**

AUG 25 1997

COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 6-3-97

Signed by Glenn E. Richard Date 6-9-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040