

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 LENAWE COUNTY  
 FILED

8 JUL 97 1:02 P.M.

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

For corners in  
Lenawee Located In: Corner Code #  
(County)

1. Public Land Survey T - 5-S R - 1 - E J-1  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on May 19, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set on original G.L.O. survey.  
 1873 Burton Kent, Co. Surveyor, surveyed Section 2 "Found the NW and NE by the witness trees"  
 "The N 1/4 post was set by dividing the North line equally"  
 1956 K. L. Suydam (employed by W. E. Frazier) set 1/2" iron pipe for N 1/4 corner Section 2  
 1974 I found iron pipe and recorded it in L 3 P 29  
 1983 K. L. Suydam found iron pipe on survey recorded in L 945 P 162  
 Sept. 1996 I found the iron pipe 12" deep and witnessed it and found iron pipe at J-13 T4S R1E 8.73 West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 19, 1997 Set point in base course of asphalt so Jackson Co. Rd. Comm. could set a monument box. I set 3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is on line between Jackson Co. monuments J-13 and K-13 T4S R1E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
 Found iron pipe South 33.16  
 Re-Rod (on same line South 72.83  
 Re-rod in fence north from J-13 T4S R1E N 10° W 80.42  
 Dbt. hd nail & re-mon tag in E. P. S 40° W 165.44  
 Dbt. hd nail & re-mon tag in E. side 11" Elm South 96.82  
 Jackson Co. Harrison monument in monument box West 8.79

	A	B	C	D	E	F	G	H	I	J	K	L	M
1										●			
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	8	7	6	5	4	3	2	1					
7													
8	9	8	7	6	5	4	3	2	1				
9													
10	10	9	8	7	6	5	4	3	2	1			
11													
12	11	10	9	8	7	6	5	4	3	2	1		
13													

SURVEY &  
 RE-MONUMENTATION

AUG 25 1997

COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 6-3-97

Signed by Glenn E. Richard Date 6-9-97  
 Glenn E. Richard

Surveyor's Michigan License No. 13040