

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee Located In: Corner Code #

(County)

- 1. Public Land Survey T-5-S R-1-E J-7
2. Property Controlling in Section S-T-R
3. Miscellaneous Property in Sec. S-T-R

STATE OF MICHIGAN LENAWEE COUNTY FILED 13 NOV 96 9:07 A.M. JEANETTE D. KNOX Register of Deeds

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell (7, I) contains a black dot.

I, Glenn E. Richard, in a field survey on August 16 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Feb. 1824 Robert Clark set Section 1/4 post W. Oak 12 S 29 E 44 W. Oak 18 N 10 E 47 Feb. 27, 1874 B. Kent survey NE 1/4 Section 14 but didn't describe type of monument at the corner April 16, 1887 J. Blair survey called for stone Aug. 1940 H. Clegg found 1" iron pipe. Set iron pipe 33' West March 22, 1972, I Dug through the pavement and found 1" iron pipe 15" deep and raised with 7/8" iron bar and recorded it in Liber 1, Page 357 June 14, 1994 Found iron bar and set witnesses stakes to save corner prior to road being torn up.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 16, 1995 Found 7/8" iron bar in bottom of new monument box set by Lenawee County Road Commission] during paving. Couldn't get it out or drive it any deeper. Must be on stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" X 2' iron pipe capped G.E.R. 13040 over 7/8" iron bar in monument box and is accepted as the best available evidence of the original corner. Re-rod at edge of trees N 55° E 71.45 dbl. hd. nail and disc in E.P. N 55° E 41.86 dbl. hd. nail and disc in 24" Oak S 45° W 88.55 dbl. hd. nail and disc in 40" Oak West 47.38 Found nail in E.P. N 50° W 37.68 Iron pipe capped G.E.R. 13040 west on Section line 33.02

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 8-6-96

Signed by Glenn E. Richard Date 10-5-96

Glenn E. Richard

Surveyor's Michigan License No. 13040

