

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 136

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5-S R 1-E J-8
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec S _____ T _____ R _____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

13 NOV 96 9:07 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on August 23 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set on the original GLO surveys
1887 James Blair did a survey in the NE 1/4 of Section 23. He ran North and South 1/4 line but didn't show anything at the center.
Oct. 1959 K.L. Suydam established a point to use on a survey West of the center
Jan 1974 W.E. Sommer re-established the point set by K.L. Suydam (P.K. in pavement)
Sept 1980 W.E. Sommer re-established the point set by K.L. Suydam (3/4" iron pipe in pavement) and recorded it in Liber 4, Page 389
June 1994 Found iron pipe & witnessed to save corner prior to road being re-constructed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 23, 1995 Set 3/4" X 3' gas pipe in monument box set by Lenawee County Road Commission during paving

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the corner.
dbl. hd. nail and disc in E.P. N 45° W 48.46
dbl. hd. nail and disc in 18" Hickory N 15° W 96.51
dbl hd. nail and disc in 40" Maple N 40° E 60.96
"X" on N. end C.M.P. N 75° E 33.61
"X" on S. end C.M.P. S 45° E 39.83



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 8-6-96

Signed by Glenn E. Richard Date _____
Glenn E. Richard

Surveyor's Michigan License No. 13040