

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 138

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5 - S R - 1 - E J-9
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
LENAAEE COUNTY  
FILED

13 NOV 96 9:07 A.M.

JEANETTE D. KNOX  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on August 23 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Feb. 1824 Robert Clark Tamarack 4 stands for 1/4 Section corner  
Oct. 1884 J. Blair found Tamarack stump under pike. Drove tooth in center.  
This corner wasn't found or re-established when the road was surveyed by H. Clegg in Aug 1940  
This corner is in a 10' fill area of the road.  
March 1974 W. Sommer re-established the corner by extending line north from boat spike found at the center of Section 26 through boat spike found at 1/8 corner and in line of occupied fence east.  
June 1994 Found iron pipe and witnessed to save corner prior to road being re-constructed  
Nov. 1994 Set 1/2" Re-rod in first course of asphalt pavement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 23, 1995 Set 3/4" X 3' gas pipe in monument box set by Lenawee County Road Commission during paving

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the corner.  
Found iron pipe East 32.89  
Found P.K. nail and flagging in east face of E.P. N 30° W 64.55  
Face of south leg of radio tower N 15° E 369.99  
Found dbl. hd. nail and disc in east face of 40" Maple S 20° W 171.26  
Re-rod N 15° E 227.58 on line with "X" cut on concrete base of radio tower N 15° E 370.26 from Section corner



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 8-6-96

Signed by Glenn E. Richard Date 10-5-96  
Glenn E. Richard

Surveyor's Michigan License No. 13040