

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 135

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5 - S R 1 - E J-10
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec S _____ T _____ R _____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

13 NOV 96 9:07 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on August 23 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set on the original Government survey
 Sept. 1880 James Blair established the corner at the intersection of the 1/4 lines at west end of bridge. Set sleigh shoe and bricks.
 Oct. 1884 J. Blair found the corner when he surveyed the Northeast 1/4 of Section 26
 J.L. Richard's records called for iron, bricks, and stone. Same witnesses as J. Blair
 1940 H. Clegg survey shows "O"
 May 1957, July 1971 & Oct. 1974 W.E. Sommer found boat spike
 Dec. 1971 K.L. Suydam survey calls for found boat spike and again in 1978
 May 1980 Found iron pipe which checked witness to boat spike
 Sept. 1989 Found iron pipe in monument box
 Aug. 1994 Found iron pipe in monument box as road was being torn up for reconstruction and set "control" east out of construction area

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 23, 1995 Set 3/4" X 3" gas pipe from 1994 "control" in monument box set by Lenawee County Road Commission during paving

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the corner.
 Dbl. hd. nail and disc in S. face of E.P. N 45° E 46.49
 Dbl. hd. nail and disc in N. face of E.P. S 75° E 137.26
 Dbl. hd. nail and disc in W. face of 24" Oak S 30° E 97.15
 Dbl. hd. nail and disc in W. face of 20" Oak S 20° W 90.96
 1/2" iron rod in road East 53.56
 1/2" re-rod West 46.33
 Corner is on line between last two witnesses



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 8-6-96

Signed by Glenn E. Richard Date 10-5-96
Glenn E. Richard

Surveyor's Michigan License No. 13040