

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

8 JUL 97 1:01 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T - 5 - S R - 1 - E	K-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	20	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on May 19, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 Robert Clark intersect N Bdg. 8 lks E. of post set post at intersection corner Sections 1 & 2 B. Oak 16 N 59 W 19.
1873 Burton Kent, Co. Surveyor, surveyed Section 2 "Found the NW and NE by the witness trees"
1956 K. L. Suydam found large stone on end. Set iron 0.30 N.
1972 Werner Sommer Found the iron pipe and stone and recorded the iron pipe in L 2 P 45 and recorded 14 surveys.
1978 K. L. Suydam recorded a survey in L 861 P 770 with same witnesses as LCRC in L 2 P 45
Sept. 24, 1996 Found iron pipe 0.3 N of 15" X 6" pointed stone and witnessed the I. P. Jackson Co. Rd. Comm. dug with back hoe but we didn't find anything else. I set the stone 1' +/- South and 2 1/2 deep as Jackson Co. Rd. Comm. was starting to rebuild road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 19, 1997 I set monument box in base course of asphalt and 3/4" X 3' gas pipe capped G.E.R. 13040 on line between K-13 and L-13 T4S R1E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
P. K. nail in top of large stone S 60° E 50.17
nail and washer in W. side 22" Maple S 10° W 67.78
Fd nail and washer in W. side 24" Oak N 45° W 43.91
N. E. corner of Hse foundation S 30° W 118.00
N. W. corner of Hse foundation S 40° W 137.14
Jackson Co. Harrison monument stamped 18658 at K-13 T4S R1E in monument box West 4.13

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 6-3-97

Signed by Glenn E. Richard Date 6-9-97
Glenn E. Richard

Surveyor's Michigan License No. 13040



SURVEY &
REMONUMENTATION
AUG 25 1997
COMMISSION