

SURVEY & REMONUMENTATION

FEB 03 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 201

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 5-S R - 1 - E	L-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED
 17 OCT 97 3:51 P.M.
 VICTORIA J. DANIELS
 Register of Deeds Stamp & Fee Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on May 19, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set on original G.L.O. survey.
 Early 1900's J. L. Richard record "stake, Jackson 1/4 post"
 1972 Werner Sommer found pinched iron pipe and recorded it in L 2 P 53
 1974 Richard Gutekunst found stone with iron on north side
 Sept. 24, 1996 I found rusted pinched iron and witnessed prior to road re-construction by Jackson Co. Rd. Comm.
 This corner has been used as a common corner with L-13 T4S R1E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 25, 1997 Dean Gutekunst dug with back hoe found iron and stone
 May 19, 1997 Dean Gutekunst PS 18658 set a Harrison monument in a monument box in the base course of asphalt road.
 May 28, 1997 I found Jackson Co. Harrison monument stamped PS 18658 in a monument box.
 July 9, 1997 Dean Gutekunst recorded this corner under the Jackson Co. remonument program in L 1546, P 466, Jackson Co. Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Jackson Co. Harrison monument in monument box stamped 18658. The position of L-1 T5S R1E was not established by original government surveyors. This monument which is L-13 T4S R1E has been used and is accepted and approved by the Peer Group as the best available evidence of the position of the corner.

Iron pipe capped G.E.R. South 32.91
 Re-rod (on same line) South 81.30
 Fd. nail and aluminum disc in SW side 42" Oak N 55° W 63.65
 Fd nail in E side 10" Ash N 25° E 41.78
 Dbl. hd nail & re-mon tag in 16" Ash S 65° W 95.67

This corner is common with L-13 T4S R1E



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 3, 1997
 Signed by Glenn E. Richard Date Oct. 7, 1997
 Surveyor's Michigan License No. 13040