

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990 LIBER 1 PAGE 202

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

17 OCT 97 3:52 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T-5-S R-1-E T-5S R-2E T- T- T- T-	M-1 A-1
2. Property Controlling in Section	S- S- S- S-	T- T- T- T-
3. Miscellaneous Property in Sec	S- S- S- S-	T- T- T- T-

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on May 19, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1815 Benjamin Hough set post corner T's 4&5 S R's 1&2 E B. Oak 18 S 1/2 E 2.10 W. Oak 14 N 80 1/2 E 143 1967 I set a iron pipe 33 feet west of a found iron pipe and recorded it in L 5 P 59, after digging through the pavement and not finding anything.
1973 Richard Gutekunst found iron in monument box
1982 I found a iron pipe in a monument box and recorded it in L 5, P 59.
Sept. 24, 1996 I found iron pipe in monument box and witnessed it.
1996 Dean Gutekunst and Jackson Co. Rd. Comm. dug hole 6' +/- E-W by 8' +/- N-S but didn't find anything.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 19, 1997 Dean Gutekunst PS 18658 set a Harrison monument in a monument box in the base course of asphalt road.
May 28, 1997 I found Jackson Co. Harrison monument stamped PS 18658 in a monument box.
July 9, 1997 Dean Gutekunst P.S. 18658 recorded this corner under the Jackson Co. remonumentation program in L 1546, P467, Jackson County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Jackson Co. Harrison monument stamped 18658 and is the best available evidence of the position of the original corner.

- " X " cut on face of N. gate post of chain link fence N 50° E 47.18
- " X " cut on face of N. gate post of chain link fence S 80° E 38.24
- " X " cut on face of S. gate post of chain link fence S 45° E 53.40
- " X " cut on S. end C.M.P. S 60° W 59.67
- " X " cut on N. end C.M.P. N 65° W 62.94

This corner is common with M-13, T4S, R1E, A-13 T4S, R2E, and A-1 T5S R2E.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 3, 1997

Signed by Glenn E. Richard Date Oct 7, 1997
Glenn E. Richard

Surveyor's Michigan License No. 13040