

FEB 16 1999

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 294
STATE OF MICHIGAN
LENAAWEE COUNTY
FILED

SECTION

For corners in

Lenawee
(County)

Located In:

Corner Code #

10 DEC 1998 9:45:37 AM

VICTORIA J. DANIELS
REGISTER OF DEEDS

- 1. Public Land Survey T - 5-S R - 1-E M-9
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on September 17, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815-16 Benj Hough set post corner Sec.'s 24 & 25 B Oak 16 N 58 E 11 B Oak 18 N 35 W 44
1886 James Blair found cedar stake and he found sleigh shoe, crockery and glass at A-9 T5S R2E
120 1/2 links (GLO=120) South of the cedar stake
1963 Kenneth Suydam found the sleigh shoe, glass & china and raised with a 1" solid shaft at A-9, T5S R2E
1975 Walter Frazier and Assoc. dug for the stake at M-9 T5S R1E but didn't find anything and set a iron pipe 120 1/2 links (76.53') north of the iron shaft at A-9 T5S R2E on extension of line from M-10 T5S R1E and Kenneth Suydam recorded it in Liber 3 Page 259
1976 Wemer Sommer "found" (type of monument not given) and found iron bar 76.55 South

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 17, 1998 I dug and found a 1" iron pipe 13" below the pavement 76.48 feet north of iron shaft. Set a 5/8" X 3' re-rod in the top of the found iron pipe and drove them both down.
Sept. 21 Set monument box in newly layed asphalt pavement

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod over 1" iron pipe with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

- Fd. dbl. hd. nail & disc in 24" Hickory N 25°W 52.80
- Fd. cotton gin spike in 24" Walnut S 60° E 122.27
- Survey mark spike with Len. Co. re-mon tag in 13" Hickory S 10° W 153.68
- Iron pipe capped W.E.F. 17636 West 32.87

A-9 T5S R2E South 76.48



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-22-98

Signed by Glenn E. Richard Date Nov. 10, 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040