

FEB 16 1999

SECTION

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 295

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

10 DEC 1998 9:45:52 AM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 5-S R - 1-E	M-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 21, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815-16 Benj Hough set 1/4 Sec. post W. Oak 24 N 41 W 13 B. Oak 12 S 6 W 52  
 1886 James Blair did survey in Section 30 T5S R2E and he found stake, crockery and stones  
 1963 Kenneth Suydam dug and found large stone, crockery and stake hole on north side of stone.  
 Set 12" X 3/4" iron pipe on top of stone & 1 1/4" X 28" iron pipe in old stake hole 0.33 north of stone.  
 Witness to south iron USGSBM N 79° 15' E 18.98. He also dug for A-10 T5S R2E but only found pieces of crockery. Blairs record called for bricks, dishes, glass, iron & stones. He then set 5/8" steel rod 58.58' (Blairs record) south from the iron on the old stake hole.  
 1972 Kenneth Suydam "Found iron pipe" and recorded it in L 1 P 213 USGSBM NE 18.79  
 1972 Werner Sommer found iron pipe as shown on survey recorded in L2 P 184 of surveys USGSBM N 82° E 18.70  
 1975 Kenneth Suydam "Found PK over iron pipe" and recorded it in L3 P 259 USGSBM N 79° 15' E 18.98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 21, 1998 I dug and found P.K. nail in the original pavement and 1" X 12" galv. pipe under the pavement leaning N.E. Found 1 1/4" iron pipe 2' below the pavement 0.05 W & 0.05 South of the location of the P.K. nail. Set 5/8" X 3' re-rod in the top of the 2' deep found iron pipe and drove them both down. Placed Lenawee County re-mon cap stamped P.S. 13040 on the re-rod and set monument box in newly layed asphalt pavement

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

- USGSBM N 80° E 18.89
- Fd. dbl. hd. nail & disc in Elec. pole N 25° E 108.20
- Fd. dbl. hd. nail & disc in 9" Quad Walnut S 35° E 40.89
- Fd. dbl. hd. nail & disc in 12" Elm S 40° W 60.42
- A-10 T5S R2E North 58.54 North



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-22-98

Signed by Glenn E. Richard Date Nov. 10, 1998  
Glenn E. Richard

Surveyor's Michigan License No. 13040