

JAN 15 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 341
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

29 SEP 1999 5:56:26 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T <u>5-S</u> R <u>1-E</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815-16, Benj. Hough Set post corner Sec. 25 & 36 W. Oak 10 S 17 1/2 E 28 B. Oak 15 N 30 W 47 1/2
Could not find any information on this corner in any of the old survey records.
1972 Wemer Sommer found the location to be in a cut area of the road. He re-established the corner (iron pipe in the pavement) by doubling the distance and extending east the monumentation on the south line of the W 1/2 of the SE 1/2 of Section 25 T5S R1E
1995 Steve Young found iron pipe
1999 Mike Bartolo found capped iron in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 23, 1999 Found iron pipe under new pavement. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Fd. nail & M. Bartolo brass tag in wood corner post S 70° E 38.82
Fd. dbl hd nail & disc in E.P. S 5° W 92.02
Set survey mark spike & re-mon tag in 8" Hickory N 60° W 36.72
Set dbl hd nail & re-mon tag at over grown nail in 16" Oak N 15° W 69.96
The corner is 3'± West of pavement centerline

A-11 T5S R2E South 40.88



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999

Signed by Glenn E. Richard Date Sept. 24, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040