

SURVEY &  
REMONUMENTATION

FEB 16 1999

LAND CORNER RECORDATION CERTIFICATE LIBER 1  
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 296  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

SECTION

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T <u>5</u> - S R - 2 - E	<u>A - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10 DEC 1998 9:46:05 AM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on September 21, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, Hervey Parke intersect W. boundary 120 lks. of post. Set post at intersection cor Sec's 19 & 30  
W. Oak 26 N 53 W 12, Y. Oak 20 S 10 1/2 W 47  
1890 James Blair found cast iron sleigh shoe, dishes and glass, center of Church door N 89 1/2 W 90 1/2 links (59.73')  
1963 Kenneth Suydam dug at Blair's record distance from the back of the Church steps (the church no longer standing) and found the sleigh shoe, glass, pieces of china and raised with 7" X 1" shaft. Nail in face of 22" Walnut S 68 E 71.73  
1973 Kenneth Suydam found 1" iron rod and recorded it in L. 2, P. 419  
1976 Werner Sommer found re-rod 76.55 South of M-9 T5S-R1E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 21, 1998 Set monument box in base course of new asphalt pavement over 3/4" steel rod  
October 14, 1998 Replaced the found 3/4" X 20" steel rod with 5/8" X 3" re-rod with Lenawee Co. re-mon cap stamped P.S. 13040 after adjusting it 0.03 East to be on line between M-9 and M-10, T5S-R1E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod Lenawee Co. re-mon cap stamped P.S. 13040 in mon. box and is accepted as the best available evidence of the position of the original corner.

Fd. cotton gin spike in 24" Walnut S 75°E 72.42  
Fd. dbl. hd. nail & disc in 14" Walnut N 65°E 78.08  
Fd. dbl. hd. nail & disc in 24" Hickory N 10°W 126.51  
Survey mark spike and re-mon tag in 13" Hickory S 20° W 79.16  
Iron pipe capped W.E.F. 17636 N 25° W 83.23

M-9 T5S-R1E, North 76.48



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 11-3-98

Signed by Glenn E. Richard Date Nov. 10, 1998  
Glenn E. Richard

Surveyor's Michigan License No. 13040