

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

8 JUL 97 1:03 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 5-S R - 2 - E	B-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on May 19, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1824 Hervey Parke set 1/4 sec. post w. Oak 28 S 84 W 17, W. Oak 10 S 20 E 24
1898 James Blair Fd. corner consisting of a stone set on top of another stone from which a W. Oak stump said to be the gov. witness bears S 84 W 17 lks
J. L. Richard records are a copy of Blair's record.
1968 I found large stone over small stone & crockery and set 1 1/4" X 5' iron bar?

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 19, 1997 Found 1 1/4" X 5' iron pipe on NE side of stone. Dug out stone & iron pipe to set Harrison monument. Found pieces of crockery 2' deep in sub soil. Replaced stone on SE side of Harrison monument. Record to Blair's iron South = 1325.61 meas. 1323.31
Replaced iron pipe with 30" Harrison monument stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040 and is accepted as a careful and faithful perpetuation of the position of the original corner.
dbl hd nail & re-mon witness tag in N side 12" Triple Maple S 80° W 49.93
dbl hd nail & re-mon witness tag in E side 10" Twin Hickory S 35° W 79.59
dbl hd nail & re-mon witness tag in E side 16" Walnut S 5° W 24.46
Face of 3" steel chain link fence post N 25° W 70.94
Face of 3" steel chain link fence post N 5° E 95.48
Carsonite survey marker post North 1.0

SURVEY &
REMONUMENTATIO

AUG 25 1997

COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 6-3-97

Signed by Glenn E. Richard Date 6-9-97
Glenn E. Richard

Surveyor's Michigan License No. 13040