

JAN 23 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 325  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

1 SEP 1999 5:41:59 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located in:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T - 5 - S R - 2 - E	C-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on June 25, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, Hervey Parke set 1/4 Sec. post W. Oak 34 N 11 W 23 W. Oak 12 S 10 E, 29  
Could not find any information on this corner  
1974 Werner Sommer found a 1" iron pipe & recorded it in L 2 P 673  
1974 Ken Suydam found iron  
1993 Werner Sommer found iron pipe  
1995 I found 3/4" galv. pipe and witnessed it prior to paving by the Lenawee County Road Commission

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 25, 1999 Dug through asphalt pavement and found 3/4" X 15" galv. pipe 15" deep.  
Found large stone 30" deep under the found 3/4" galv. pipe. Bent the bottom 12" of a 5/8" X 3' re-rod and drove it with the bent bottom on the north side of the stone. Set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod over stone with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Fd. dbl. hd. nail & disc in 16" W. Cherry N 85° W 38.01  
"X" cut on CMP N 5° W 146.00  
"X" cut on CMP N 5° E 146.47  
Fd. capped iron pipe (GER 13040) East 33.00 on East and West 1/4 line Section 29



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999

Signed by Glenn E. Richard Date Aug. 2, 1999  
Glenn E. Richard

Surveyor's Michigan License No. 13040