

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5 - S R - 2 - E C-11
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec S T R

LIBER 1 PAGE 344

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

29 SEP 1999 5:57:09 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11		●											
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824, Hervey Parke set post corner Sec. 29, 30, 31 & 32 Y. Oak 34 S 39 E 40 W. Oak 30 N 14 1/2 W 41
- Could not find any information on this corner in any of the old survey records.
- 1935 Walter Frazier surveyed Slee Rd. "Set hub" S 56 W NE corner of stone porch 99.7
- 1967 The corner was re-established by Gillespie and Associates
- 1972 Werner Sommer found iron and recorded it in Liber 1, Page 679
- 1974 Kenneth Suydam did a survey in Section 29 and labeled the corner as "Found iron"
- 1995 Steve Young found iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 19, 1999 I found a 3/4" X 12" iron pipe 10" deep under base course of new asphalt pavement. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- NE corner of stone porch S 50° W 90.42
- Fd. 60d spike in 24" Locust S 15° W 60.78
- Set dbl hd nail & Lenawee County Re-mon tag in 24" Locust S 10° E 87.35
- Fd. dbl hd nail & Aluminum disc E.P. N 50° E 70.72



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999
 Signed by Glenn E. Richard Date Sept. 24, 1999
 Surveyor's Michigan License No. 13040