

JAN 25 2000

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1

PAGE 345
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5-S</u> R <u>2-E</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

29 SEP 1999 5:57:34 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 20, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824, Hervey Parke set 1/4 Sec. post W. Oak 20 N 72 W 85 W. Ash 8 S 23 W 43
- Could not find any information on this corner in any of the old survey records.
- 1935 Walter Frazier surveyed Slee Rd. but didn't find any corner
- ? Walter Frazier did a survey in Section 29 & labeled S 1/4 corner (type of monumentation not given)
- 1949 Harold Clegg and I did a survey in Sec. 29 & labeled S 1/4 corner (type of monumentation not given)
- 1954 Kenneth Suydam and I did a survey in Sec. 29 & labeled S 1/4 corner (type of monumentation not given)
- 1974 Werner Sommer found a boat spike and recorded it in Liber 2, Page 675
- 1974 Kenneth Suydam did a survey in Sec. 29 and shows same witnesses as recorded in Liber 2, page 675
- 1995 Steve Young found boat spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 20, 1999 I found a boat spike under base course of new asphalt pavement. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- SE corner of stone porch N 70° E 177.74
- set dbl hd nail & Lenawee County re-mon tag in E.P. S 85° W 248.58
- Fd dbl hd nail & disc in R.R. tie post North 35.76
- Fd. dbl hd & disc in E.P. South 26.81

The corner is 1' North of pavement centerline



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999
Signed by Glenn E. Richard Date Sept. 24, 1999
Glenn E. Richard
Surveyor's Michigan License No. 13040