

JAN 15 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5 - S R 2 - E E-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec S _____ T _____ R _____

LIBER 1 PAGE 346
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

29 SEP 1999 5:57:47 PM

VICTORIA J. DANIELS
Register of Deeds

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 20, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824, Hervey Parke set 1/4 Sec. post W. Oak 18 N 53 1/2 W 59 W. Oak 18 S 46 E 40
- Could not find any information on this corner in any of the old survey records.
- 1935 Walter Frazier surveyed Slee Road but didn't find any corner
- 1972 Kenneth Suydam's survey recorded in Liber 1 of Surveys on Page 278 calls for iron pipe. The notes don't show whether set or found.
- 1974 Werner Sommer found 1" iron pipe and recorded it in Liber 2, Page 675
- 1995 Steve Young found iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 20, 1999 Found iron pipe under base course of asphalt pavement. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd 60d spike in N. face of E.P. S 45° W 47.15
- Fd. nail & disc in NE face of E.P. S 45° W 47.02
- Fd dbl hd nail & disc in 14" Oak S 35° E 74.26
- Set dbl hd nail & re-mon tag in 22" Oak S 5° W 127.05
- East edge of stop sign post N 25° W 43.29

The corner is 0.5 North of pavement centerline



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999

Signed by Glenn E. Richard Date Sept. 24, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040