

JAN 20 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 347
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T-5-S R-2-E	F-11
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

29 SEP 1999 5:57:58 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 20, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, Hervey Parke set 1/4 Sec. post Maple 16 N 75 E 85 W. Ash 8 S 59 1/2 E 52
Could not find any information on this corner in any of the old survey records.
1935 Walter Frazier surveyed Slee Rd. but didn't find anything
1974 Werner Sommer re-established the corner (3/4" iron pipe in the pavement) by westerly extension of the south line of the Assessor's Plat of Onsted and in line of fence to the south and recorded it in Liber 2, Page 619.
1995 Steve Young found 3/4" iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 20, 1999 Found 3/4" X 13" iron pipe under base course of asphalt pavement.
Replaced with 5/8" X 3" re rod with Lenawee County re-mon cap stamped P.S. 13040 and set a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3" re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner

Survey mark spike & Lenawee County Re-mon tag in E. face 58" Oak North 119.34
South edge of steel guard post for catch basin N 45° E 24.84
"X" cut on top of conc. project post S 30° E 32.80
"X" cut on face of steel post South 34.19

The corner is 1.5' North of pavement centerline



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 14, 1999

Signed by Glenn E. Richard Date Sept. 23, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040