

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE LIBER 1 PAGE 148

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

3 DEC 96 3:23 P.M.

JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 5-S R 2-E      G-4  
                                          T \_\_\_\_\_ R \_\_\_\_\_  
                                          T \_\_\_\_\_ R \_\_\_\_\_  
                                          T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 14 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1824, Joseph Mack set 1/4 Sec. post W. Oak 30 N 61 W 20, W. Oak 18 S 70 E 27  
 Nov. 1888, James Blair renewed the corner by driving down a piece of twisted lightning rod S 61 W 20 lks. from a 40" W. Oak, one of the government witness trees.  
 J.L. Richard records describe the corner as iron & bricks, 38" W. Oak N 61 W 20 lks.  
 May 1921, Walter Frazier "Found no trace. Drove iron in line with E. & W. fences and in Center between N. & S. road fences" SW. Corner of house NE 1.28 ch. (84.48'), 18" Locust SE 34.0  
 1951, Harold Clegg and I found iron pipe 1.7 deep & the notes show the same witnesses as the Walter Frazier survey.  
 1958 is P.O.B. for Plat of SIAM, Rec. in L. 14 of Plats, Pages 27 & 28.  
 Nov. 1978, I found an iron pipe 12" deep, raised to the surface with a 1/2" iron pipe and recorded it in L. 4, P. 195.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 14, 1996, (My 66th Birthday) I dug through new asphalt pavement and found 3/4" X 12" iron pipe over 1/2" X 24" over 1 1/4" iron pipe 3 feet deep.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" gas pipe capped G.E. R. in monument box and is accepted as the best available evidence of the position of the original corner.  
 Found nail with ribbon in 36" Locust S 40° E 34.97  
 Found nail with ribbon in 28" Locust S 80° W 29.03  
 Dbl. hd. nail & Re-mon tag in Elec. pole N 50° W 126.32  
 SE. corner of brick chimney Hse. #11489 N 35° W 116.08  
 SW. corner of stone foundation Hse. #11487 N 60° E 83.47  
 The corner is 3' ± West of the east edge of the pavement.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-29-1996

Signed by Glenn E. Richard Date Nov. 27, 1996  
 Glenn E. Richard

Surveyor's Michigan License No. 13040