

COMMISSION

For corners in Lenawee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 5-S R 2-E K-6
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

FILED
 NOV 22 1995 11:56 AM
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on August 29, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. 1824, Harvey Parke set 1/4 sec. post W. Oak 10 S 65 E W Oak 6 S 31 W 25 November 1883, James Blair re-established the corner and set stake, bricks and iron December 1971, W.E. Frazier & Associates re-established the corner by extending line from the East and set 1 1/4" X 16" solid iron bar and K.L. Suydam recorded it in Liber 01, Page 223. May 1980, Associated Engineers & Surveyors found the 1 1/4" solid iron bar which checked the recorded witnesses. July 1993, The road was under construction and I found the 1 1/4" solid iron bar tipped over and set a 3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in hole found in the subsoil of where it had been. May 1995, M. Bartolo found the 3/4" gas pipe under the asphalt and raised it with a 1/2" X 9" iron pipe and recorded it in Liber 5, Page 265.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 August 29, 1995 Found iron pipe as recorded in Liber 5, Page 265 over my 3/4" X 3" gas pipe. Removed Bartolo's iron pipe and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 3/4" X 3" gas pipe capped G.E.R. P.S. 13040 in monument box as is accepted as the best available evidence of the position of the original corner.
 "X" on East end 15" C.M.P. N 60° W 52.60
 "X" on West end 15" C.M.P. N 65° W 74.27
 Dbl. hd. nail & disc in West face of 10" Oak North 39.16
 Dbl. hd. nail & disc in NW face of 8" Walnut N 60° E 67.16
 Center line of pavement North 8.5' ±



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-19-95
 Signed by Glenn E. Richard Date Nov. 3, 1995
 Surveyor's Michigan License No. 13040