

JAN 25 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1

PAGE 332  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

SECTION

For corners in Lenawee Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T - 5 - S R - 3 - E G-10  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1 SEP 1999 5:43:29 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Glenn E. Richard, in a field survey on June 4, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O. 1824, John Mack set 1/4 Sec. post W. Ash 7 N 33 E 7 Sugar 4 S 58 W 10  
1842 S.C. Boughton subdivided Section 28 "corners found"  
1920 J.L. Richard record "stones found"  
1972 The corner falls in a cut area. I re-established it by retracement of previous surveys in the NW 1/4 of Section 27. (Set 3/4" X 2' iron pipe in the pavement) and recorded it in L1 P 517

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
June 4, 1999 Found 60g spike in top of iron pipe. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 & set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

dbl. hd nail & Lenawee County re-mon tag in EP S 25° W 213.05  
Survey mark spike & Lenawee County re-mon tag in EP N 45° W 129.85  
dbl. hd. nail & Lenawee County re-mon tag in 12" Elm N 85 E 45.47  
Cut "X" on CMP S 5° W 113.62



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999

Signed by Glenn E. Richard Date Aug. 23, 1999  
Glenn E. Richard

Surveyor's Michigan License No. 13040