

JUL 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1

PAGE 334
STATE OF MICHIGAN
LENAAWEE COUNTY
FILED

SECTION

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T -5- S R -3- E	G-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

1 SEP 1999 5:43:55 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 7, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824, John Mack set 1/4 Sec. post W. Oak 30 N 47 W 18 Hickory 10 N 54 E 16 ,
- 1886 James Blair found stone
- 1920 J.L. Richard surveyed Tipton Hwy. and called for the corner in his description
- 1973 Wemer Sommer set a iron pipe by retracing J.L. Richard's survey of Tipton Hwy. using his two centerline P.I.'s to the south at the town line and recorded it in Liber 2, Page 347
- 1999 Mike Bartolo found 60d spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 7, 1999 Found 60d spike in top of iron pipe 3" deep. Replaced them with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 & set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd nail & disc in T.P. stub N 45° W 38.29
- Fd. dbl. hd. nail & disc in 24" Maple S 55° W 45.95
- Fd. dbl. hd. nail & disc in E.P. S 65° E 57.04
- Fd. dbl. hd. nail & disc & added re-mon tag in 24" Maple S 20° W 66.40



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999

Signed by Glenn E. Richard Date Aug. 23, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040