

JAN 12 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 335
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

Lenawee
(County)

Located In:

Corner Code #

| | | | | | | | |
|------------------------------------|---|---|---|---|---|---|------|
| 1. Public Land Survey | T | 5 | S | R | 3 | E | G-13 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Sec | S | | T | | R | | |
| | S | | T | | R | | |

1 SEP 1999 5:44:11 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Glenn E. Richard, in a field survey on June 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John Mack set post corner Sec.'s 33 & 34 8 chs (528') E of old corner B. Ash 12 N 38 W 43 Basswood 5 S 44 E 18 NOTE: The GLO map and notes for subdivision of T6S R3E call for a jog of 640 links=422.40 feet

1880 James Blair "commencing at the NW corner of Sec. 3 T6S R3E and running N 88 1/4 E 7.82 chains, pass SW corner Section 34 T5S R3E." (Type of monumentation not given)

1886 James Blair found the corner "stone and bricks"

1915 J.L. Richard found stones & bricks

1920 J.L. Richard surveyed Tipton Hwy. (Type of monumentation not given)

1935 Walter Frazier did survey in sections 3 & 4 T6S R3E and witnessed the corner to concrete headwalls on driveway culvert

1960 Kenneth Suydam resurveyed Tipton Hwy. and set 8" boat spike using the witnesses from the 1935 survey and set iron pipe S 89° W 32.89 & spike & washer in W. face of Walnut East 41.40

1963 Kenneth Suydam set a 1" steel shaft using the 1960 information

1973 Werner Sommer found 1" steel shaft which checked the distance on the 1880 Blair survey West (G.L.O. 640 links=422.40 Blair 516.12 meas 516.35) to found stone and iron pipe at the NW corner of Section 3 T6S R3E and recorded it in Liber 2, Page 347

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 7, 1999 I found a PK nail in the pavement 0.07 E & 0.10 N of a 1" iron bar 6" deep. Replaced the iron bar with 5/8" X 3' re-rod with Lenawee County re-mon cap & set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

FIP S 89° W 32.98
 Fd nail & washer in W. face of 24" Walnut N 88° E 41.17
 Fd. dbl. hd. nail & disc in N. face of 24" Walnut N 88° E 42.33
 Cut "X" on S. end CMP S 50° E 25.31
 Survey mark spike in E. face 12" Hickory N 10° W 190.15



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999

Signed by Glenn E. Richard Date Aug. 23, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040